

Kentucky Housing Corporation

Weatherization Assistance Program (WAP) Guidance

March 25, 2021

KHC Program Notice 01-2021

1. Subject: Installation of vapor barrier on mobile homes:

Guidance: In accordance with the SWS 2.0202.1: Vapor barrier shall be installed to achieve 100% coverage of exposed crawl space, shall overlap a minimum of 12” at all seams using a reverse or upslope lapping technique, installed on foundation piers a minimum of 6” above interior grade, and secured to foundation walls a minimum of 6” above interior grade. Vapor barrier is not required to be secured to any type mobile home skirting material. Vapor barrier under a mobile home shall be brought to the skirting and secured to achieve 100% coverage of exposed crawl space.

2. Subject: Updated QCI Inspection Form

Guidance: Effective March 29, 2021 QCI and DNE staff performing evaluations or final inspections must use the March 2021 version of the Kentucky WAP QCI Final Inspection Checklist form (attached). The QCI Final Inspection Checklist must be completed and signed by the appropriate inspector and maintained in the client file.

KHC PN Guidance Distributed By:	
TECHNICAL: Deanna McCord Manager - REE 800-633-8896 or (502) 564-7630, Ext. 344 dmccord@kyhousing.org	ADMINISTRATIVE: Keli Reynolds Manager – Single Family & HCA Support 800-633-8896 or (502) 564-7630, Ext. 414 kreynolds@kyhousing.org